LEGEND

SOFT LANDSCAPE

Existing Trees and Hedges to be Retained
Please refer back to arboricultural report. Trees to be retained in line with BS5837:2012 .

Existing Trees Removed
Please refer back to arboricultural report.

Proposed Medium Trees
Trees to comprise of native and ornamental species,12-14cm girth Heavy Standards, 350-400cm height, with 2m clear stem.

Proposed native tree
Native trees to be planted as feathered whips 175 - 200cm height. Trees to be planted and secured in place with double timber stakes , cross bar and tree ties.

Proposed Ornamental Planting
Shrubs and herbaceous plants to be planted as 3L pots at 3-5 per sq.m to soften the built form and provide seasonal interest.

Proposed Specimen Shrub Planting
Specimen shrubs to be planted individually as 10-25L pots within the ornamental shrub beds for added height and visual interest.

Proposed Raingardens
Proposed rain gardens to be planted with water tolerant species suitable for SuDS. Subject to detailed design by drainage engineers.

Amenity Grass
Existing amenity grass to remain

Species Rich Grass
Areas of existing amenity grass to be topdressed and seeded with species rich grass mix.

Native shrub planting
Native shrubs planted at 1/m2

HARD LANDSCAPE

Proposed Block Paving to Walkways
To be 200x100x60mm concrete block paving in herringbone pattern to walkways. Subject to design by highways engineer.

Proposed Paving Slabs around Building
Paving units proposed to be 450 x 450 x 35mm textured finish concrete flags.

Proposed Tarmac
Main access roads and paths to be surfaced in black tarmacadam.

Proposed Stepping Stones
Large flush stepping stones to be laid within the gravel in between the rain gardens to create an informal path. Subject to detailed design.

Proposed Gravel
Grey 10mm granite chippings to margins, 50mm depth. To be laid on weed suppressing membrane.

Revision Notes
Rev P01 : Stg 2 issue 03.06.26
Rev P02 : Stg 2 issue 08.06.26
Cycle store orientated to avoid viz splay
minor parking adjustments to accommodate tracking
Rev P03 : Stg 3 issue 18.06.26
Native Planting Added
Bin store / M&E moved approx 2 spaces to ensure avoidance of RPA.

DEP LANDSCAPE ARCHITECTURE LTD
2 COMMERCIAL STREET
MANCHESTER, M15 4RQ
T: 0161 2419878
E: info@dep.co.uk
W: www.dep.co.uk

Client
Cityheart

Project
Wrexham University Campus

Description
Landscape Proposals

Status
S2 Suitable for Information

Scale	Drawn
1 : 250@A1	BH

Job number	Drawing number	Date	Revision
WREX-DEP-XX-XX-DR-L-0001			P03

Copyright DEP Landscape Architecture Ltd

All levels and dimensions to be checked on site by contractor prior to commencement; Any variations to be reported to the client. This drawing is to be read in conjunction with all others relating to the project and all information derived accordingly; any anomolies to be reported to the client. Do not scale from this drawing. Use figured dimensions only. Work shown on this drawings to be carried out in accordance with current British Standards and Codes of Practice.

© Copyright to DEP Landscape Architecture Limited. The information shown on this drawing shall not be reproduced or copied in any form without prior written consent from DEP Landscape Architecture Limited.